

EXACT®

STRAIGHT EDGE RULE SE-48

CONSTRUCTION NOTES

- ① CONST. BRIDGE PER DETAILS SH#13,14,19
- ② CONST. 2" A.C./A.B.
- ③ CONST. METAL BEAM GUARD RAIL PER DETAILS SH#19
- ④ REMOVE DETOUR EAST AND GRADE CHANNEL PER DETAILS SH#13,14,15
- ⑤ REMOVE AND SALVAGE 36" C.M.P. AT DETOUR EAST.
- ⑥ PROTECT ROCK WALL IN PLACE
- ⑦ PROTECT CONC. RESERVOIR IN PLACE
- ⑧ PLACE JOINT AT STA 10+00 (C. CHECK)
- ⑨ SEC. U-G DETAIL SH#13
- ⑩ REMOVE DETOUR WEST AND GRADE CHANNEL TO JOIN O.G.
- ⑪ REMOVE AND SALVAGE 36" C.M.P. AT DETOUR WEST.

APPROXIMATE BRIDGE QUANTITIES

1. 36" C.M.P. TEMPORARY DETOUR CULV.	88 L.F.
2. TEMPORARY GUIDE MARKERS	43 ea.
3. REMOVE BRIDGE SV-14	L.S.
4. IMPORTED BORROW	80 C.Y.
5. ROADWAY EXCAVATION	993 C.Y.
6. STRUCTURE EXCAVATION	230 C.Y.
7. STRUCTURE BACKFILL	204 C.Y.
8. AGGREGATE BASE	89 Ton
9. ASPHALT CONCRETE	195 Ton
10. CLASS 'A' CONCRETE	240 C.Y.
11. BAR REINFORCING STEEL	22,213 lbs.
12. METAL BEAM BARRIER RAIL	126 L.F.

