



DEPARTMENT OF TRANSPORTATION
Structure Maintenance & Investigations

Bridge Number : 55C0097
Facility Carried: TALBERT/MACARTHUR
Location : 0.6 MI W/O HARBOR BLVD.
City :
Inspection Date : 05/05/2010

Bridge Inspection Report

Inspection Type

Routine	FC	Underwater	Special	Other
☒	☐	☐	☐	☐

STRUCTURE NAME: SANTA ANA RIVER CHANNEL

CONSTRUCTION INFORMATION

Year Built : 1983	Skew (degrees): 30
Year Widened: N/A	No. of Joints : 2
Length (m) : 110	No. of Hinges : 0

Structure Description: Continuous 4 span CIP/RC box girder (8 cells) with RC pier walls and RC open end seat abutments, all supported upon concrete piles.

Span Configuration : (W) 24.4 m, 2 @ 29.9 m, 24.4 m (E) c/c

LOAD CAPACITY AND RATINGS

Design Live Load: MS-18 OR HS-20	
Inventory Rating: 32.4 metric tonnes	Calculation Method: NO RATING ANALYSIS
Operating Rating: 54.1 metric tonnes	Calculation Method: NO RATING ANALYSIS
Permit Rating : P P P P P	
Posting Load : Type 3: Legal	Type 3S2: Legal Type 3-3: Legal

DESCRIPTION ON STRUCTURE

Deck X-Section: (S) 0.3 m br, 1.5 m sw, 20.8m, 1.5 m sw, 0.3 m br (N)
Total Width: 24.4 m Net Width: 20.7 m No. of Lanes: 4
Rail Description: Type 26 Conc. Rail Code : 1000
Min. Vertical Clearance: Unimpaired

DESCRIPTION UNDER STRUCTURE

Channel Description: RC trapezoidal.

CONDITION TEXT

CONDITION OF STRUCTURE

There are unsealed transverse cracks throughout the deck moderate in size (0.5 mm - 2 mm) and density (300 mm spacing).

There are 3 minor (0.5 mm) and 1 moderate (1 mm) vertical cracks in pier walls 2, 3, and 4.

There was 100 mm water in the deepest section of the concrete channel; all elements were inspected.

ELEMENT INSPECTION RATINGS

F#Elem	Element Description	Env	Total Units		Qty in each Condition State				
			Qty		St. 1	St. 2	St. 3	St. 4	St. 5
101 12	Concrete Deck - Bare	2	2250	sq.m.	2250	0	0	0	0
101 105	Reinforced Concrete Closed Webs/Box Girder	2	110	m.	110	0	0	0	0
101 210	Reinforced Conc Pier Wall	2	84	m.	84	0	0	0	0
101 215	Reinforced Conc Abutment	2	56	m.	56	0	0	0	0
101 256	Slope Protection	2	2	ea.	2	0	0	0	0
101 302	Compression Joint Seal	2	48	m.	48	0	0	0	0
101 312	Enclosed/Concealed Bearing	2	2	ea.	2	0	0	0	0

F#Elem	Element Description	Env	Total	Units	Qty in each Condition State				
					Qty	St. 1	St. 2	St. 3	St. 4
101 331	Reinforced Conc Bridge Railing	2	222	m.	222	0	0	0	0
101 358	Deck Cracking	2	1	ea.	0	0	1	0	0

WORK RECOMMENDATIONS

RecDate: 06/07/2007

EstCost:

Seal the deck cracks with methacrylate.

Action : Deck-Methacrylate

StrTarget: 2 YEARS


Work By: LOCAL AGENCY

DistTarget:

Status : PROPOSED

EA:

Inspected By : A.Shenouda/MT.Zaarour



Registered Civil Engineer



STRUCTURE INVENTORY AND APPRAISAL REPORT

***** IDENTIFICATION *****

(1) STATE NAME- CALIFORNIA 069
 (8) STRUCTURE NUMBER 55C0097
 (5) INVENTORY ROUTE (ON/UNDER) - ON 1400M0340
 (2) HIGHWAY AGENCY DISTRICT 12
 (3) COUNTY CODE 059 (4) PLACE CODE 00000
 (6) FEATURE INTERSECTED- SANTA ANA RIVER CHANNEL
 (7) FACILITY CARRIED- TALBERT/MACARTHUR
 (9) LOCATION- 0.6 MI W/O HARBOR BLVD.
 (11) MILEPOINT/KILOMETERPOINT 0
 (12) BASE HIGHWAY NETWORK- PART OF NET 1
 (13) LRS INVENTORY ROUTE & SUBROUTE 000000M03400
 (16) LATITUDE 33 DEG 42 MIN 07 SEC
 (17) LONGITUDE 117 DEG 55 MIN 48 SEC
 (98) BORDER BRIDGE STATE CODE % SHARE %
 (99) BORDER BRIDGE STRUCTURE NUMBER

***** STRUCTURE TYPE AND MATERIAL *****

(43) STRUCTURE TYPE MAIN:MATERIAL- CONCRETE CONT
 TYPE- BOX BEAM OR GIRDER - MULTI CODE 205
 (44) STRUCTURE TYPE APPR:MATERIAL- OTHER/NA
 TYPE- OTHER/NA CODE 000
 (45) NUMBER OF SPANS IN MAIN UNIT 4
 (46) NUMBER OF APPROACH SPANS 0
 (107) DECK STRUCTURE TYPE- CIP CONCRETE CODE 1
 (108) WEARING SURFACE / PROTECTIVE SYSTEM:
 A) TYPE OF WEARING SURFACE- NONE CODE 0
 B) TYPE OF MEMBRANE- NONE CODE 0
 C) TYPE OF DECK PROTECTION- NONE CODE 0

***** AGE AND SERVICE *****

(27) YEAR BUILT 1983
 (106) YEAR RECONSTRUCTED 0000
 (42) TYPE OF SERVICE: ON- HIGHWAY-PEDESTRIAN 5
 UNDER- WATERWAY 5
 (28) LANES:ON STRUCTURE 04 UNDER STRUCTURE 00
 (29) AVERAGE DAILY TRAFFIC 26000
 (30) YEAR OF ADT 2002 (109) TRUCK ADT 1 %
 (19) BYPASS, DETOUR LENGTH 2 KM

***** GEOMETRIC DATA *****

(48) LENGTH OF MAXIMUM SPAN 29.9 M
 (49) STRUCTURE LENGTH 110.0 M
 (50) CURB OR SIDEWALK: LEFT 1.5 M RIGHT 1.5 M
 (51) BRIDGE ROADWAY WIDTH CURB TO CURB 20.7 M
 (52) DECK WIDTH OUT TO OUT 24.4 M
 (32) APPROACH ROADWAY WIDTH (W/SHOULDERS) 20.7 M
 (33) BRIDGE MEDIAN- NO MEDIAN 0
 (34) SKEW 30 DEG (35) STRUCTURE FLARED NO
 (10) INVENTORY ROUTE MIN VERT CLEAR 99.99 M
 (47) INVENTORY ROUTE TOTAL HORIZ CLEAR 20.7 M
 (53) MIN VERT CLEAR OVER BRIDGE RDWY 99.99 M
 (54) MIN VERT UNDERCLEAR REF- NOT H/RR 0.00 M
 (55) MIN LAT UNDERCLEAR RT REF- NOT H/RR 0.0 M
 (56) MIN LAT UNDERCLEAR LT 0.0 M

***** NAVIGATION DATA *****

(38) NAVIGATION CONTROL- NOT APPLICABLE CODE N
 (111) PIER PROTECTION- CODE
 (39) NAVIGATION VERTICAL CLEARANCE 0.0 M
 (116) VERT-LIFT BRIDGE NAV MIN VERT CLEAR M
 (40) NAVIGATION HORIZONTAL CLEARANCE 0.0 M

***** SUFFICIENCY RATING *****

SUFFICIENCY RATING = 94.5
 STATUS
 HEALTH INDEX 100.0
 PAINT CONDITION INDEX = N/A

***** CLASSIFICATION ***** CODE

(112) NBIS BRIDGE LENGTH- YES Y
 (104) HIGHWAY SYSTEM- NOT ON NHS 0
 (26) FUNCTIONAL CLASS- OTHER PRIN ART URBAN 14
 (100) DEFENSE HIGHWAY- NOT STRAHNET 0
 (101) PARALLEL STRUCTURE- NONE EXISTS N
 (102) DIRECTION OF TRAFFIC- 2 WAY 2
 (103) TEMPORARY STRUCTURE-
 (105) FED.LANDS HWY- NOT APPLICABLE 0
 (110) DESIGNATED NATIONAL NETWORK - NOT ON NET 0
 (20) TOLL- ON FREE ROAD 3
 (21) MAINTAIN- COUNTY HIGHWAY AGENCY 02
 (22) OWNER- COUNTY HIGHWAY AGENCY 02
 (37) HISTORICAL SIGNIFICANCE- NOT ELIGIBLE 5

***** CONDITION ***** CODE

(58) DECK 5
 (59) SUPERSTRUCTURE 7
 (60) SUBSTRUCTURE 7
 (61) CHANNEL & CHANNEL PROTECTION 9
 (62) CULVERTS N

***** LOAD RATING AND POSTING ***** CODE

(31) DESIGN LOAD- MS-18 OR HS-20 5
 (63) OPERATING RATING METHOD- NO RATING ANALYSIS 5
 (64) OPERATING RATING- 54.1
 (65) INVENTORY RATING METHOD- NO RATING ANALYSIS 5
 (66) INVENTORY RATING- 32.4
 (70) BRIDGE POSTING- EQUAL TO OR ABOVE LEGAL LOADS 5
 (41) STRUCTURE OPEN, POSTED OR CLOSED- A
 DESCRIPTION- OPEN, NO RESTRICTION

***** APPRAISAL ***** CODE

(67) STRUCTURAL EVALUATION 7
 (68) DECK GEOMETRY 9
 (69) UNDERCLEARANCES, VERTICAL & HORIZONTAL N
 (71) WATER ADEQUACY 9
 (72) APPROACH ROADWAY ALIGNMENT 8
 (36) TRAFFIC SAFETY FEATURES 1000
 (113) SCOUR CRITICAL BRIDGES 8

***** PROPOSED IMPROVEMENTS *****

(75) TYPE OF WORK- CODE
 (76) LENGTH OF STRUCTURE IMPROVEMENT M
 (94) BRIDGE IMPROVEMENT COST
 (95) ROADWAY IMPROVEMENT COST
 (96) TOTAL PROJECT COST
 (97) YEAR OF IMPROVEMENT COST ESTIMATE
 (114) FUTURE ADT 53226
 (115) YEAR OF FUTURE ADT 2029

***** INSPECTIONS *****

(90) INSPECTION DATE 05/10 (91) FREQUENCY 24 MO
 (92) CRITICAL FEATURE INSPECTION: (93) CFI DATE
 A) FRACTURE CRIT DETAIL- NO MO A)
 B) UNDERWATER INSP- NO MO B)
 C) OTHER SPECIAL INSP- NO MO C)