



DEPARTMENT OF TRANSPORTATION
Structure Maintenance & Investigations

Bridge Number : 55C0183
Facility Carried: BELHA WAY
Location : 50' N/O SILVERADO CYN RD
City :
Inspection Date : 12/20/2015

Bridge Inspection Report

Inspection Type
Routine FC Underwater Special Other

☒

STRUCTURE NAME: SILVERADO CANYON CREEK

CONSTRUCTION INFORMATION

Year Built : 1963 Skew (degrees): 21
Year Widened: N/A No. of Joints : 0
Length (m) : 7 No. of Hinges : 0

Structure Description: Single span PC/PS concrete cored slab units (3 each) with RC open end seat abutments, all supported upon spread footings.

Span Configuration : (S) 1 @ 6.4 m (N) c/c

SAFE LOAD CAPACITY AND RATINGS

Design Live Load: UNKNOWN
Inventory Rating: RF=0.75 =>24.3 metric tons Calculation Method: FIELD EVAL/ENG JUDGMENT
Operating Rating: RF=1.25 =>40.5 metric tons Calculation Method: FIELD EVAL/ENG JUDGMENT
Permit Rating : PPPPP
Posting Load : Type 3: Legal Type 3S2: Legal Type 3-3: Legal

DESCRIPTION ON STRUCTURE

Deck X-Section: (W) 0.2 m br, 3.5 m, 0.2 m br (E)
Total Width: 3.9 m Net Width: 3.5 m No. of Lanes: 1 Speed: 25 mph
Min. Vertical Clearance: Unimpaired Overlay Thickness: 4.0 Inches
Rail Code: 1000

Rail Type	Location	Length (ft)	Rail Modifications
MBBR	Right/Left	46	

DESCRIPTION UNDER STRUCTURE

Channel Description: Natural earth trapezoidal with a cobbled bottom and with a concreted bottom through the site.

NOTICE

The bridge inspection condition assessment used for this inspection is based on the American Association of State Highway and Transportation Officials (AASHTO) Bridge Element Inspection Manual 2013 as defined in Moving Ahead for Progress in the 21st Century (MAP-21) federal law. The new element inspection methodology may result in changes to related condition and appraisal ratings on the bridge without significant physical changes at the bridge.

The element condition information contained in this report represents the current condition of the bridge based on the most recent routine and special inspections. Some of the notes presented below may be from an inspection that occurred prior to the date noted in this report. Refer to the Scope and Access section of this inspection report for a description of which portions of the bridge were inspected on this date.

INSPECTION COMMENTARY

SCOPE AND ACCESS

The water in the channel is 8" deep, so all visible substructure elements were visually inspected. Pedestrian access is from north east quadrant.

SUPERSTRUCTURE

INSPECTION COMMENTARY

There is growing vegetation at the west abutment wall and soffit between the slab units.

SAFE LOAD CAPACITY

A Load Rating Summary Sheet archived on 02/10/2014 is on file for this structure. The current rating has been assigned in accordance with SMI procedures for concrete bridges without plans.

ELEMENT INSPECTION RATINGS AND NOTES										
Elem No.	Defect /Prot	Defect	Element Description	Env	Total Qty	Units	Qty in each Condition State			State
							St. 1	St. 2	St. 3	St. 4
39			Slab-PS Conc.	2	28	sq.m	28	0	0	0
	510		Deck Wearing Surface-Asphalt	2	25	sq.m	25	0	0	0
(39)										
There were no significant defects noted.										
(39-510)										
There were no significant defects noted.										
215			Abutment-RC	2	8	m	8	0	0	0
(215)										
There were no significant defects noted.										
330			Railing-Metal	2	14	m	14	0	0	0
(330)										
There were no significant defects noted.										

WORK RECOMMENDATIONS - NONE

Team Leader : Ashraf Shenouda
 Report Author : Ashraf Shenouda
 Inspected By : A.Shenouda/KD.Henderson

Ashraf Shenouda 3/11/2016
 Ashraf Shenouda (Registered Civil Engineer) (Date)



STRUCTURE INVENTORY AND APPRAISAL REPORT

***** IDENTIFICATION *****

(1) STATE NAME- CALIFORNIA 069
 (8) STRUCTURE NUMBER 55C0183
 (5) INVENTORY ROUTE(ON/UNDER)- ON 140000000
 (2) HIGHWAY AGENCY DISTRICT 12
 (3) COUNTY CODE 059 (4) PLACE CODE 00000
 (6) FEATURE INTERSECTED- SILVERADO CANYON CREEK
 (7) FACILITY CARRIED- BELHA WAY
 (9) LOCATION- 50' N/O SILVERADO CYN RD.
 (11) MILEPOINT/KILOMETERPOINT 0
 (12) BASE HIGHWAY NETWORK- NOT ON NET 0
 (13) LRS INVENTORY ROUTE & SUBROUTE
 (16) LATITUDE 33 DEG 44 MIN 46.83 SEC
 (17) LONGITUDE 117 DEG 35 MIN 38.69 SEC
 (98) BORDER BRIDGE STATE CODE % SHARE %
 (99) BORDER BRIDGE STRUCTURE NUMBER

***** STRUCTURE TYPE AND MATERIAL *****

(43) STRUCTURE TYPE MAIN:MATERIAL- CONCRETE
 TYPE- SLAB CODE 101
 (44) STRUCTURE TYPE APPR:MATERIAL- OTHER/NA
 TYPE- OTHER/NA CODE 000
 (45) NUMBER OF SPANS IN MAIN UNIT 1
 (46) NUMBER OF APPROACH SPANS 0
 (107) DECK STRUCTURE TYPE- PRECAST CONC. PA CODE 2
 (108) WEARING SURFACE / PROTECTIVE SYSTEM:
 A) TYPE OF WEARING SURFACE- BITUMINOUS CODE 6
 B) TYPE OF MEMBRANE- NONE CODE 0
 C) TYPE OF DECK PROTECTION- NONE CODE 0

***** AGE AND SERVICE *****

(27) YEAR BUILT 1963
 (106) YEAR RECONSTRUCTED 0000
 (42) TYPE OF SERVICE: ON- HIGHWAY 1
 UNDER- WATERWAY 5
 (28) LANES:ON STRUCTURE 01 UNDER STRUCTURE 00
 (29) AVERAGE DAILY TRAFFIC 100
 (30) YEAR OF ADT 2009 (109) TRUCK ADT 1 %
 (19) BYPASS, DETOUR LENGTH 199 KM

***** GEOMETRIC DATA *****

(48) LENGTH OF MAXIMUM SPAN 6.4 M
 (49) STRUCTURE LENGTH 7.0 M
 (50) CURB OR SIDEWALK: LEFT 0.0 M RIGHT 0.0 M
 (51) BRIDGE ROADWAY WIDTH CURB TO CURB 3.5 M
 (52) DECK WIDTH OUT TO OUT 3.9 M
 (32) APPROACH ROADWAY WIDTH (W/SHOULDERS) 3.7 M
 (33) BRIDGE MEDIAN- NO MEDIAN 0
 (34) SKEW 21 DEG (35) STRUCTURE FLARED NO
 (10) INVENTORY ROUTE MIN VERT CLEAR 99.99 M
 (47) INVENTORY ROUTE TOTAL HORIZ CLEAR 3.5 M
 (53) MIN VERT CLEAR OVER BRIDGE RDWY 99.99 M
 (54) MIN VERT UNDERCLEAR REF- NOT H/RR 0.00 M
 (55) MIN LAT UNDERCLEAR RT REF- NOT H/RR 0.0 M
 (56) MIN LAT UNDERCLEAR LT 0.0 M

***** NAVIGATION DATA *****

(38) NAVIGATION CONTROL- NOT APPLICABLE CODE N
 (111) PIER PROTECTION- CODE
 (39) NAVIGATION VERTICAL CLEARANCE 0.0 M
 (116) VERT-LIFT BRIDGE NAV MIN VERT CLEAR M
 (40) NAVIGATION HORIZONTAL CLEARANCE 0.0 M

SUFFICIENCY RATING = 65.1
 STATUS
 HEALTH INDEX 100.0
 PAINT CONDITION INDEX = N/A

***** CLASSIFICATION ***** CODE

(112) NBIS BRIDGE LENGTH- YES Y
 (104) HIGHWAY SYSTEM- NOT ON NHS 0
 (26) FUNCTIONAL CLASS- COLLECTOR URBAN 17
 (100) DEFENSE HIGHWAY- NOT STRAHNET 0
 (101) PARALLEL STRUCTURE- NONE EXISTS N
 (102) DIRECTION OF TRAFFIC- 1 LANE, 2 WAY 3
 (103) TEMPORARY STRUCTURE-
 (105) FED.LANDS HWY- NOT APPLICABLE 0
 (110) DESIGNATED NATIONAL NETWORK - NOT ON NET 0
 (20) TOLL- ON FREE ROAD 3
 (21) MAINTAIN- COUNTY HIGHWAY AGENCY 02
 (22) OWNER- COUNTY HIGHWAY AGENCY 02
 (37) HISTORICAL SIGNIFICANCE- NOT ELIGIBLE 5

***** CONDITION ***** CODE

(58) DECK 8
 (59) SUPERSTRUCTURE 8
 (60) SUBSTRUCTURE 8
 (61) CHANNEL & CHANNEL PROTECTION 8
 (62) CULVERTS N

***** LOAD RATING AND POSTING ***** CODE

(31) DESIGN LOAD- UNKNOWN 0
 (63) OPERATING RATING METHOD- FIELD EVAL/ENG JUD 0
 (64) OPERATING RATING- 40.5
 (65) INVENTORY RATING METHOD- FIELD EVAL/ENG JUL 0
 (66) INVENTORY RATING- 24.3
 (70) BRIDGE POSTING- EQUAL TO OR ABOVE LEGAL LOADS 5
 (41) STRUCTURE OPEN, POSTED OR CLOSED- A
 DESCRIPTION- OPEN, NO RESTRICTION

***** APPRAISAL ***** CODE

(67) STRUCTURAL EVALUATION 6
 (68) DECK GEOMETRY 3
 (69) UNDERCLEARANCES, VERTICAL & HORIZONTAL N
 (71) WATER ADEQUACY 9
 (72) APPROACH ROADWAY ALIGNMENT 6
 (36) TRAFFIC SAFETY FEATURES 1000
 (113) SCOUR CRITICAL BRIDGES 5

***** PROPOSED IMPROVEMENTS *****

(75) TYPE OF WORK- MISC STRUCTURAL WORK CODE 38
 (76) LENGTH OF STRUCTURE IMPROVEMENT 7 M
 (94) BRIDGE IMPROVEMENT COST \$26,000
 (95) ROADWAY IMPROVEMENT COST \$5,200
 (96) TOTAL PROJECT COST \$43,680
 (97) YEAR OF IMPROVEMENT COST ESTIMATE 2010
 (114) FUTURE ADT 105
 (115) YEAR OF FUTURE ADT 2035

***** INSPECTIONS *****

(90) INSPECTION DATE 12/15 (91) FREQUENCY 24 MO
 (92) CRITICAL FEATURE INSPECTION: (93) CFI DATE
 A) FRACTURE CRIT DETAIL- NO MO A)
 B) UNDERWATER INSP- NO MO B)
 C) OTHER SPECIAL INSP- NO MO C)