



### ADA Survey Summary

| Item | Description                           | Quantity | EA | SY | LF | IN |
|------|---------------------------------------|----------|----|----|----|----|
| 1    | Vertical Displacement <= 1"           | 4        | EA |    |    |    |
| 2    | Vertical Displacement > 1"            | 0        | EA |    |    |    |
| 3    | Uneven Vertical Displacement          | 0        | EA |    |    |    |
| 4    | Horizontal Opening > 0.5"             | 0        | EA |    |    |    |
| 5    | Poor Surface Condition                | 0        | SY |    |    |    |
| 6    | Utility Obstruction                   | 0        | EA |    |    |    |
| 7    | Power Pole Obstruction                | 1        | EA |    |    |    |
| 8    | Traffic Signal Obstruction            | 0        | EA |    |    |    |
| 9    | Sign Obstruction                      | 1        | EA |    |    |    |
| 10   | Low Vegetative Obstruction            | 0        | EA |    |    |    |
| 11   | Overhead Vegetative Obstruction       | 0        | EA |    |    |    |
| 12   | Other Obstruction*                    | 0        | EA |    |    |    |
| 13   | Miscellaneous Obstruction             | 0        | EA |    |    |    |
| 14   | Temp/Private Obstruction              | 0        | EA |    |    |    |
| 15   | Commercial Driveway                   | 0        | LF |    |    |    |
| 16   | Residential Driveway                  | 44       | LF |    |    |    |
| 17   | Total Sidewalk Length Assessed        | 190      | LF |    |    |    |
| 18   | Average Sidewalk Width                | 60       | IN |    |    |    |
| 19   | Curb Ramps In Corridor                | 2        | EA |    |    |    |
| 20   | Island Curb Cuts In Corridor          | 0        | EA |    |    |    |
| 21   | Signal Push Buttons In Corridor       | 0        | EA |    |    |    |
| 22   | Accessible Parking Spaces In Corridor | 0        | EA |    |    |    |
| 23   | Missing Sidewalk/Gaps in Connectivity | 0        | LF |    |    |    |
| 24   | Buried/Narrow Sidewalk                | 0        | LF |    |    |    |
| 25   | Sidewalk Not Surveyed                 | 0        | LF |    |    |    |
| 26   | No Sidewalk Observed                  | 0        | LF |    |    |    |
| 27   | Corridor Severity Score               | 37.11    |    |    |    |    |

Google Street View Link  
[http://www.google.com/maps/@?api=1&map\\_action=pano&viewpoint=33.74330205,-117.80567987](http://www.google.com/maps/@?api=1&map_action=pano&viewpoint=33.74330205,-117.80567987)

### ADA Compliance Cost Estimate \*\*

| Item          | Description   | Quantity | Unit | Unit Price | Item Cost           |
|---------------|---|----------|------|------------|---------------------|
| 1             | Vertical Displacement <= 1"                             | 1        | EA   | \$150.00   | \$ 150.00           |
| 2             | Vertical Displacement > 1"                              | 0        | EA   | \$2125.00  | \$ 0.00             |
| 3             | Uneven Vertical Displacement                            | 0        | EA   | \$2125.00  | \$ 0.00             |
| 4             | Horizontal Opening > 0.5"                               | 0        | EA   | \$1062.00  | \$ 0.00             |
| 5             | Poor Surface Condition                                  | 0        | SY   | \$255.50   | \$ 0.00             |
| 6             | Utility Obstruction                                     | 0        | EA   | \$5000.00  | \$ 0.00             |
| 7             | Power Pole Obstruction                                  | 1        | EA   | \$20000.00 | \$ 20000.00         |
| 8             | Traffic Signal Obstruction                              | 0        | EA   | \$5000.00  | \$ 0.00             |
| 9             | Sign Obstruction  | 1        | EA   | \$2000.00  | \$ 2000.00          |
| 10            | Low Vegetative Obstruction                              | 0        | EA   | \$200.00   | \$ 0.00             |
| 11            | Overhead Vegetative Obstruction                         | 0        | EA   | \$400.00   | \$ 0.00             |
| 12            | Other Obstruction*                                      | 0        | EA   | \$2000.00  | \$ 0.00             |
| 13            | Miscellaneous Obstruction                               | 0        | EA   | \$2000.00  | \$ 0.00             |
| 14            | Commercial Driveway                                     | 0        | LF   | \$118.00   | \$ 0.00             |
| 15            | Residential Driveway                                    | 44       | LF   | \$118.00   | \$ 5288.00          |
| 16            | Running Slope Violation                                 | 0        | SY   | \$255.50   | \$ 0.00             |
| 17            | Cross Slope Violation                                   | 42       | SY   | \$255.50   | \$ 10977.00         |
| 18            | Running and Cross Slope violations                      | 0        | SY   | \$255.50   | \$ 0.00             |
| 19            | Non-Compliant Curb Ramps and Total Cost*                | 2        | EA   | VARIABLES  | \$ 7080.00          |
| 20            | Non-Compliant Island Curb Cuts and Total Cost*          | 0        | EA   | VARIABLES  | \$ 0.00             |
| 21            | Non-Compliant Signal Push Buttons Cuts and Total Cost*  | 0        | EA   | VARIABLES  | \$ 0.00             |
| 22            | Non-Compliant Accessible Parking Spaces and Total Cost* | 0        | EA   | VARIABLES  | \$ 0.00             |
| 23            | Missing Sidewalk/Gap in Connectivity                    | 0        | SY   | \$150.00   | \$ 0.00             |
| 24            | Buried/Narrow Sidewalk                                  | 0        | SY   | \$255.50   | \$ 0.00             |
| <b>Total:</b> |   |          |      |            | <b>\$ 45,496.00</b> |

#### Compliance Symbology

- Compliant Curb Ramp
- Non-Compliant Curb Ramp
- Compliant Island Curb Cut
- Non-Compliant Island Curb Cut
- Compliant Signal
- Non-Compliant Signal

#### Running Slope (Deviated, Costed)

- 5.1 – 8.3%
- 8.4 – 10.0%
- 10.1 – 12.5%
- 12.5%+

#### Cross Slope

- 2.01 - 3.0%
- 3.01 - 4.0%
- 4.01 - 5.0%
- 5.01%+

\*Note: Some items combined for display. See Unit Cost Table for specific unit costs for each type of obstruction, curb ramp, island curb cut. Missing sidewalk/gaps in connectivity reported together in compliance report and are separate in the GIS layers.  
 \*\*Note: ADA pedestrian issues have been identified and quantified in the ADA Survey Summary. There are instances where multiple issues can be resolved with a single corrective measure. The ADA Compliance Cost Estimate reflects the best estimation of quantities and cost to resolve all identified ADA issues.