



Access Compliance Report Public Rights-of-Way (Curb Ramps)



Main Street: HAZARD_AVE Cross Street: NEWLAND_ST Location: NW

ADA ID: RPAT220221144730 Ramp Type: Type 4 - Parallel Initial Pass/Fail: Pass Overall Compliance: No Severity Score: 20

Codes/Mitigation Info/Possible Solution

Field Measurements/Component Compliance



Possible Solutions:

Remove & Replace Curb Ramp With Two New Directional Ramps or Equivalent. Remove & Replace Gutter. Utility Present.

Surveyor Notes:

N/A

OC Std/PROW:

R304.2.2, R302.7, R304.5.4, STD 1115

Total Cost: \$ 4252

Parcel ID Number 097-183-12
Ramp Island Or Median None
Ramp Orientation Diag
Google Street View Link:

http://www.google.com/maps/@?api=1&map_action=pano&viewpoint=33.75215794,-117.98114984

Street 1 Name HAZARD_AVE
Stop Condition-Street 1 Signal
Street 2 Name NEWLAND_ST
Stop Condition-Street 2 Signal

Obstruction and Utility Measurement/Component Compliance

Compliance	Description	Data	Compliance	Description	Data
Yes	Obstructions Present?	No	N/A	Utilities Present?	Yes
	Obstruction Types	N/A		Utility Types	
	Obstruction Dimensions	N/A		Traffic Signal Pole	

Compliance	Description	Data	Compliance	Description	Data
N/A	Ramp Length LT (in)	126	N/A	Ramp Length RT (in)	114
Yes	Ramp Width LT (in)	75	Yes	Ramp Width RT (in)	69
Yes	Ramp Run Slope LT (%)	6.9	Yes	Ramp Run Slope RT (%)	5
Yes	Ramp Cross Slope LT (%)	1	Yes	Ramp Cross Slope RT (%)	1
N/A	Landing Present	Yes	Yes	DWS Provided	Yes
N/A	Landing Length (in)	64	Yes	DWS Contrast	Yes
Yes	Landing Width (in)	48	Yes	DWS Length (in)	36
Yes	Landing Run Slope (%)	0.4	Yes	DWS Full Width	Yes
Yes	Landing Cross Slope (%)	1.8		DWS Offset Type	Single
N/A	Landing Movement Obstructed?	No	Yes	DWS Offset Left (in)	0
	Landing Movement Type	Curb	Yes	DWS Offset Right (in)	N/A
N/A	Landing Shared	No			
Yes	Clear Space	Yes			
Yes	Clear Space To Crosswalk (in)	48			
N/A	Marked Crosswalk 1	Yes	N/A	Marked Crosswalk 2	Yes
	Crossing 1 Direction	S		Crossing 2 Direction	E
	Marked Crosswalk 1 Width (in)	132		Marked Crosswalk 2 Width (in)	132
Yes	Ramp Inside Crosswalk 1	Yes	Yes	Ramp Inside Crosswalk 2	Yes
	Crossing 1 Slope (%)	0.4		Crossing 2 Slope (%)	3.4
	Crossing 1 Cross Slope (%)	1.4		Crossing 2 Cross Slope (%)	0.6
Yes	Gutter Ponding	No	No	Curb Slope	9.4
Yes	Gutter Lip Height (in)	0		Road Run Slope (%)	0.9
No	Gutter Run Slope (%)	5.6		Road Cross Slope (%)	3.1
Yes	Gutter Cross Slope (%)	0.1	Yes	Perpendicular Joint Present	Yes
No	Overall Surface Condition	Poor			
	Cross Gutter Present?	Yes		Spandrel Present?	Yes
	Replace Cross Gutter?	No		Replace Spandrel?	No

