



# Access Compliance Report Public Rights-of-Way (Curb Ramps)



Main Street: N/A Cross Street: ASCENSO\_AVE Location: W

ADA ID: RPRK211122130623 Ramp Type: Type 6 - Directional 1 Initial Pass/Fail: Pass Overall Compliance: No Severity Score: 4

## Codes/Mitigation Info/Possible Solution

## Field Measurements/Component Compliance



Possible Solutions:

Remove & Replace Landing.

Surveyor Notes:

N/A

OC Std/PROW:

R304.2.1, STD 1115

Total Cost:

\$ 531

Parcel ID Number 741-591-84

Ramp Island Or Median None

Ramp Orientation NonDiag

Google Street View Link:

[http://www.google.com/maps/@?api=1&map\\_action=pano&viewpoint=33.52604859,-117.62324408](http://www.google.com/maps/@?api=1&map_action=pano&viewpoint=33.52604859,-117.62324408)

Street 1 Name N/A

Stop Condition-Street 1 NoControl

Street 2 Name ASCENSO\_AVE

Stop Condition-Street 2 N/A

## Obstruction and Utility Measurement/Component Compliance

| Compliance | Description            | Data | Compliance | Description        | Data |
|------------|------------------------|------|------------|--------------------|------|
| Yes        | Obstructions Present?  | No   | N/A        | Utilities Present? | No   |
|            | Obstruction Types      | N/A  |            | Utility Types      |      |
|            | Obstruction Dimensions | N/A  |            |                    | N/A  |

| Compliance | Description                   | Data       | Compliance | Description                   | Data    |
|------------|-------------------------------|------------|------------|-------------------------------|---------|
| N/A        | Ramp Length (in)              | 108        | Yes        | Flare Type LT                 |         |
| Yes        | Ramp Width (in)               | 48         |            |                               | Curbed2 |
| Yes        | Ramp Run Slope (%)            | 6.7        | N/A        | Flare Slope LT (%)            | N/A     |
| Yes        | Ramp Cross Slope (%)          | 0.9        | N/A        | Flare Traversable LT          | N/A     |
| Yes        | Grade Break                   | Yes        | N/A        | Flare Type RT                 |         |
| Yes        | Grade Break Slope (%)         | 3          |            |                               | Sloped  |
| Yes        | Grade Break Cross Slope (%)   | 2.3        | N/A        | Flare Slope RT (%)            | 5.9     |
|            | Addl Para Ramp Left?          | No         | N/A        | Flare Traversable RT          | No      |
|            | Addl Para Ramp Right?         | No         | Yes        | DWS Provided                  | Yes     |
| N/A        | Landing Present               | Yes        | Yes        | DWS Contrast                  | Yes     |
| No         | Landing Length (in)           | 47         | Yes        | DWS Length (in)               | 72      |
| Yes        | Landing Width (in)            | 49         | Yes        | DWS Full Width                | Yes     |
| Yes        | Landing Run Slope (%)         | 0.5        |            | DWS Offset Type               | Single  |
| Yes        | Landing Cross Slope (%)       | 2.4        | Yes        | DWS Left Offset (in)          | 0       |
| N/A        | Landing Movement Obstructed?  | No         | N/A        | DWS Right Offset (in)         | 0       |
|            | Landing Movement Type         | N/A        |            |                               |         |
| N/A        | Landing Shared                | No         |            |                               |         |
| N/A        | Marked Crosswalk 1            | No         | N/A        | Clear Space                   | N/A     |
|            | Crossing 1 Direction          | SE         | N/A        | Clear Space To Crosswalk (in) | N/A     |
|            | Marked Crosswalk 1 Width (in) | N/A        |            |                               |         |
| N/A        | Ramp Inside Crosswalk 1       | N/A        |            |                               |         |
|            | Crossing 1 Slope (%)          | 2.9        |            |                               |         |
|            | Crossing 1 Cross Slope (%)    | 4.1        |            |                               |         |
| Yes        | Gutter Ponding                | No         | Yes        | Curb Slope                    | 4.2     |
| Yes        | Gutter Lip Height (in)        | 0          |            | Road Run Slope (%)            | N/A     |
| Yes        | Gutter Run Slope (%)          | 3.1        |            | Road Cross Slope (%)          | N/A     |
| Yes        | Gutter Cross Slope (%)        | 1          |            | Parallel Ramp Side            | Left    |
| Yes        | Overall Surface Condition     | Acceptable | Yes        | Perp Joint Present            | Yes     |
|            | Cross Gutter Present?         | No         |            | Spandrel Present?             | No      |
|            | Replace Cross Gutter?         | N/A        |            | Replace Spandrel?             | N/A     |

