

Access Compliance Report Public Rights-of-Way (Curb Ramps)



Main Street: BEACHMONT AVE **Cross Street: BRENAN_WAY** Location:

Overall Compliance: No ADA ID: RPRK220125124602 Ramp Type: Type 4 - Parallel Initial Pass/Fail: Fail **Severity Score:** 32

Codes/Mitigation Info/Possible Solution



Possible Solutions:

Remove & Replace Curb Ramp With Two New **Directional Ramps or Equivalent. Grind Gutter**

Surveyor Notes:

N/A

OC Std/PROW:

R204.3, R304.3.2, R304.5.3, R302.7, R302.7.2, STD


Total Cost: 4150

| Parcel ID Number | 395-473-06 | Street 1 Name | BEACHMONT_AVE |
|--------------------------|------------|-------------------------|---------------|
| Ramp Island Or Median | None | Stop Condition-Street 1 | NoControl |
| Ramp Orientation | Diag | Street 2 Name | BRENAN_WAY |
| Google Street View Link: | | Stop Condition-Street 2 | NoControl |

http://www.google.com/maps/@?api=1&map_action=pano&viewpoint=33.76125622,-117.8110093

Obstruction and Utility Measurement/Component Compliance

| Compliance Description Data | | | Compliance Description Da | | |
|-----------------------------|------------------------|-----|---------------------------|--------------------|-----|
| Yes | Obstructions Present? | No | N/A | Utilities Present? | No |
| | Obstruction Types | N/A | | Utility Types | |
| | Obstruction Dimensions | N/A | | | N/A |







| Field Measurements/Component Compliance | | | | | | | |
|---|------------------------|-------------------------------|------|-----|------------------------|------------------------|------|
| | Compliance Description | | Data | Com | Compliance Description | | Data |
| | N/A | Ramp Length LT (in) | 172 | N/A | Ramp L | ength RT (in) | 142 |
| | Yes | Ramp Width LT (in) | 86 | Yes | Ramp V | /idth RT (in) | 93 |
| | No | Ramp Run Slope LT (%) | 8.4 | Yes | Ramp R | un Slope RT (%) | 3.3 |
| | No | Ramp Cross Slope LT (%) | 3.2 | Yes | Ramp C | ross Slope RT (%) | 1.5 |
| | N/A | Landing Present | N/A | N/A | DWS Pr | rovided | N/A |
| | N/A | Landing Length (in) | N/A | N/A | DWS C | ontrast | N/A |
| | N/A | Landing Width (in) | N/A | N/A | DWS Le | ength (in) | N/A |
| | N/A | Landing Run Slope (%) | N/A | N/A | DWS Fu | ıll Width | N/A |
| | N/A | Landing Cross Slope (%) | N/A | | DWS O | ffset Type | N/A |
| | N/A | Landing Movement Obstructed? | N/A | N/A | DWS O | ffset Left (in) | N/A |
| | | Landing Movement Type | N/A | N/A | DWS O | ffset Right (in) | N/A |
| | N/A | Landing Shared | N/A | | | | |
| | N/A | Clear Space | Yes | | | | |
| | N/A | Clear Space To Crosswalk (in) | N/A | | | | |
| 0 | N/A | Marked Crosswalk 1 | No | N/A | Marked | Crosswalk 2 | No |
| | | Crossing 1 Direction | NE | | Crossin | g 2 Direction | NW |
| E | | Marked Crosswalk 1 Width (in) | N/A | | Marked | Crosswalk 2 Width (in) | N/A |
| ı | N/A | Ramp Inside Crosswalk 1 | N/A | N/A | Ramp Ir | nside Crosswalk 2 | N/A |
| Y | | Crossing 1 Slope (%) | 3.2 | | Crossin | g 2 Slope (%) | 5.3 |
| ı | | Crossing 1 Cross Slope (%) | 3.1 | | Crossin | g 2 Cross Slope (%) | 0.3 |
| | N/A | Gutter Ponding | N/A | N/A | Curb Slo | ope | 3.4 |
| | No | Gutter Lip Height (in) | 1 | | Road R | un Slope (%) | 2.1 |
| | N/A | Gutter Run Slope (%) | N/A | | Road C | ross Slope (%) | 1 |
| <u>a</u> | N/A | Gutter Cross Slope (%) | N/A | No | Perpend | licular Joint Present | No |
| ٥ | No | Overall Surface Condition | Poor | | | | |
| | | Cross Gutter Present? | Yes | | Spandr | el Present? | Yes |
| 4 | | Replace Cross Gutter? | No | | Replace | e Spandrel? | No |