


Access Compliance Report Public Rights-of-Way (Curb Ramps)



15

Main Street: DONNIE_ANN_RD **Cross Street: DONNIS RD** NW Location:

ADA ID: RPRK220217172305 Ramp Type:Type 1 - Perpendicular Diagonal Initial Pass/Fail: Pass **Overall Compliance: No Severity Score:**



Possible Solutions:

Remove & Replace Curb Ramp With Two New Directional Ramps or Equivalent. Remove & Replace Gutter.

Surveyor Notes:

N/A

OC Std/PROW:

R204.3, R305, R302.7, R304.5.4, STD 1115

Total Cost: 6412

Parcel ID Number	086-543-13	Street 1 Name	DONNIE_ANN_RD
Ramp Island Or Median	None	Stop Condition-Street 1	NoControl
Ramp Orientation	Diag	Street 2 Name	DONNIS_RD
Google Street View Link:		Stop Condition-Street 2	NoControl

http://www.google.com/maps/@?api=1&map_action=pano&viewpoint=33.80102753,-118.07771458

Obstruction and Utility Measurement/Component Compliance

Com	pliance Description	Data	Com	pliance	Description	<u>Data</u>	
Yes	Obstructions Present?	No	N/A	Utilities	Present?	No	
	Obstruction Types	N/A		Utility T	ypes		
	Obstruction Dimensions	N/A	l			N/A	



		Field Measureme	ents/C	Comp	onent Compliance	
	Com	pliance Description	Data	Com	pliance Description	Data
	N/A	Ramp Length (in)	84	N/A	Flare Type LT	
	Yes	Ramp Width (in)	48			Sloped
	Yes	Ramp Run Slope (%)	7.8	N/A	Flare Slope LT (%)	8.6
	Yes	Ramp Cross Slope (%)	0.7	N/A	Flare Traversable LT	No
	N/A	Landing Present	Yes	N/A	Flare Type RT	
	N/A	Landing Length (in)	48			Sloped
	Yes	Landing Width (in)	48	N/A	Flare Slope RT (%)	8.5
	Yes	Landing Run Slope (%)	1.4	N/A	Flare Traversable RT	No
	Yes	Landing Cross Slope (%)	0.1	No	DWS Provided	No
	N/A	Landing Movement Obstructed?	No	N/A	DWS Contrast	N/A
		Landing Movement Type	N/A	N/A	DWS Length (in)	N/A
	N/A	Landing Shared	No	N/A	DWS Full Width	N/A
	N/A	Clear Space	Yes	N/A	DWS Offset Left (in)	N/A
	N/A	Clear Space To Crosswalk (in)	48	N/A	DWS Offset Right (in)	N/A
2	N/A	Marked Crosswalk 1	No	N/A	Marked Crosswalk 2	No
		Crossing 1 Direction	S		Crossing 2 Direction	E
D		Marked Crosswalk 1 Width (in)	N/A		Marked Crosswalk 2 Width (in)	N/A
l	N/A	Ramp Inside Crosswalk 1	N/A	Yes	Ramp Inside Crosswalk 2	N/A
D		Crossing 1 Slope (%)	4.8		Crossing 2 Slope (%)	5.1
l		Crossing 1 Cross Slope (%)	0.7		Crossing 2 Cross Slope (%)	1
	No	Gutter Ponding	Yes	Yes	Curb Slope	0.9
	Yes	Gutter Lip Height (in)	0		Road Run Slope (%)	1.3
	No	Gutter Run Slope (%)	5.3		Road Cross Slope (%)	6
<u>a</u>	Yes	Gutter Cross Slope (%)	1.3			
0	Yes	Overall Surface Condition: Accep	otable	No	Perp Joint Present	No
		Cross Gutter Present?	No		Spandrel Present?	No
Α		Replace Cross Gutter?	N/A		Replace Spandrel?	N/A