

**GPS #:** 4437R1

Date Destroyed:

Date Revised: 4/5/2005

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 992/E-1

City / Location: San Clemente

Scale Factor: 0.99995633

Ellipsoid Red. Factor: 0.99999718

Combination Factor: 0.99995350

Convergence Angle: -00 46 09.55939

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 27 14.36348	117 38 59.98328	2111681.154	6134665.175	
2007.00	33 27 14.38049	117 38 59.99895	2111682.89	6134663.87	

References: RSB 151/1-11, CR 2004-1157, CR 2004-1369

**Description:**

FD PK NAIL AND WASHER STAMPED "LS 6970" IN LIEU OF PUNCHED SPIKE WITH TIN AND WASHER, STAMPED "RCE 26120", FLUSH. MONUMENT WAS RESET PER CORNER RECORD # 2004-1369. STATION IS LOCATED AT APPARENT CENTERLINE RADIUS POINT OF CALLE GRANDE VISTA CUL-DE-SAC, 300'+/- NW'LY FROM ITS INTER WITH CALLE QUIETO.

