

GPS #: **5119R3**

Date Destroyed:

Date Revised: 4/15/2012

Benchmark Designation:

OCS Index Map: 4LB

Page/Grid: 826/F-5

City / Location: Seal Beach

Scale Factor: 0.99997889

Ellipsoid Red. Factor: 1.00000518

Combination Factor: 0.99998407

Convergence Angle: -01 00 56.92595

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

NO PHOTO

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 44 15.43886	118 05 54.79342	2217004.628	5999696.249	
2007.00	33 44 15.45523	118 05 54.81058	2217006.31	5999694.83	

References: PMB 218/33-34, RSB 150/1-9, CR 2001-0769, CR 2004-1216, CR 2007-2358, CR 2009-0115, CR 2010-0342, CR 2011-3210

Description:

REESTABLISHED GEAR SPIKE WITH TAG STAMPED "LS 5411", FLUSH PER CR 2011-3210, IN LIEU OF FD SPIKE AND WASHER STAMPED "LS 7707, FLUSH IN LIEU OF PUNCHED SPIKE AND 1-1/2" BRASS OCS WASHER STAMPED "5119R1 3-01" FLUSH, ORIGINAL MONUMENT BEING PUNCHED SPIKE AND ALUMINUM WASHER, STAMPED "LS 5203". MONUMENT LOCATED AT THE CENTERLINE INTER OF OCEAN AVE. AND ELECTRIC AVE.

