

Designation: 1G-129-69

Date Destroyed:

Date Revised:

GPS #:

OCS Index Map: Q11-01

Page/Grid: 828/C-4

City / Location: Westminster

Line #/SSN: 157/0170

Established By: OCS 1969

Monument Type: Orange County Surveyor's 3 3/4"
Aluminum Disk



NAVD88 (ft)	NGVD29 (ft)	Year Leveled
40.100	37.685	2005
40.212	37.774	1992

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 44 16.31	117 58 19.27

Description:

DESCRIBED BY OCS 2002 - FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "1G-129-69", SET IN THE SOUTHWEST CORNER OF A 4 FT. BY 15 FT. CONCRETE CATCH BASIN. MONUMENT IS LOCATED IN THE NORTHEAST CORNER OF THE INTERSECTION OF MCFADDEN AVENUE AND MAGNOLIA STREET, 114 FT. NORTHERLY OF THE CENTERLINE OF MCFADDEN AVENUE AND 43 FT. EASTERLY OF THE CENTERLINE OF MAGNOLIA STREET. MONUMENT IS SET LEVEL WITH THE SIDEWALK.

