

Designation: 1G-140-69

Date Destroyed:

Date Revised:

GPS #: 1545

OCS Index Map: Q06-05

Page/Grid: 768/B-7

City / Location: Anaheim

Line #/SSN: 157/0060

Established By: OCS 1969

Monument Type: Orange County Surveyor's 3 3/4"
Aluminum Disk



NAVD88 (ft)	NGVD29 (ft)	Year Leveled
84.582	82.162	2005
84.680	82.216	1990

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 49 03.78005	117 58 31.72830

Description:

DESCRIBED BY OCS 2002 - FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "1G-140-69", SET IN THE NORTHWESTERLY CORNER OF A 16 FT. BY 4 FT. CONCRETE CATCH BASIN. MONUMENT IS LOCATED IN THE NORTHEASTERLY CORNER OF THE INTERSECTION OF BALL ROAD AND MAGNOLIA STREET, 46 FT. NORTHERLY OF THE CENTERLINE OF BALL, AND 107 FT. EASTERLY OF THE CENTERLINE OF MAGNOLIA. MONUMENT IS SET LEVEL WITH THE SIDEWALK.

