

## Designation: 1H-140-82

Date Destroyed:

Date Revised:

GPS #:

OCS Index Map: Q05-16

Page/Grid: 797/G-7

City / Location: Westminster

Line #/SSN: 158/0180

Established By: OCS 1982

Monument Type: Orange County Surveyor's 3 3/4"  
Aluminum Disk



NAVD88 (ft)	NGVD29 (ft)	Year Leveled
38.548	36.130	2005
38.682	36.224	1989

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 46 07.61	118 00 57.11

### Description:

DESCRIBED BY OCS 2002 - FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "1H-140-82", SET IN THE TOP OF A CONCRETE WINGWALL. MONUMENT IS LOCATED IN THE SOUTHEASTERLY CORNER OF THE INTERSECTION OF NAVAJO ROAD AND EDWARDS STREET, 52 FT. EASTERLY OF THE CENTERLINE OF EDWARDS STREET AND 50.5 FT. SOUTHERLY OF THE CENTERLINE OF NAVAJO ROAD. MONUMENT IS SET LEVEL WITH THE TOP OF THE WALL.

