

## Designation: 1K-23-70

Date Destroyed:

Date Revised:

GPS #:

OCS Index Map: Q06-08

Page/Grid: 769/C-5

City / Location: Anaheim

Line #/SSN: 160/0030

Established By: OCS 1970

Monument Type: Orange County Surveyor's 3 3/4"  
Aluminum Disk



NAVD88 (ft)	NGVD29 (ft)	Year Levelled
182.370	179.954	2006
182.402	179.978	1990

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 50 10.80	117 53 22.61

### Description:

DESCRIBED BY OCS 2002 - FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "1K-23-70", SET IN THE TOP OF A 6 IN. BY 6 IN. CONCRETE POST. MONUMENT IS LOCATED IN THE SOUTHWESTERLY CORNER OF THE INTERSECTION OF SANTA ANA STREET AND STATE COLLEGE BOULEVARD, 106 FT. WESTERLY OF THE CENTERLINE OF STATE COLLEGE BOULEVARD AND 21 FT. SOUTHERLY OF THE CENTERLINE OF SANTA ANA STREET. MONUMENT IS SET LEVEL WITH THE SIDEWALK.

