

Designation: 1K-30-82

Date Destroyed:

Date Revised:

GPS #:

OCS Index Map: Q06-08

Page/Grid: 769/C-5

City / Location: Anaheim

Line #/SSN: 160/0020

Established By: OCS 1982

Monument Type: Orange County Surveyor's 3 3/4"
Aluminum Disk



| NAVD88 (ft) | NGVD29 (ft) | Year Leveled |
|-------------|-------------|--------------|
| 177.857 | 175.441 | 2006 |
| 177.883 | 175.454 | 1990 |
| | | |
| | | |

| For Reconnaissance Only! | |
|--------------------------|---------------------|
| Latitude (30' +/-) | Longitude (30' +/-) |
| 33 49 53.38 | 117 53 24.44 |

Description:

DESCRIBED BY OCS 2002 - FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "1K-30-82", SET IN THE TOP OF A 6 IN. BY 6 IN. CONCRETE POST. MONUMENT IS LOCATED IN THE SOUTHWESTERLY CORNER OF THE INTERSECTION OF SOUTH STREET AND STATE COLLEGE BOULEVARD, 21 FT. SOUTHERLY OF THE CENTERLINE OF SOUTH STREET, 273 FT. WESTERLY OF THE CENTERLINE OF STATE COLLEGE BOULEVARD AND 1 FT. SOUTHERLY OF THE CURB FACE. MONUMENT IS SET UP 0.2 FT. ABOVE THE SIDEWALK.

