

## Designation: 2A-36-70

Date Destroyed:

Date Revised:

GPS #:

OCS Index Map: Q03-15

Page/Grid: 740/D-4

City / Location: Yorba Linda

Line #/SSN: 251/0050

Established By: OCS 1970

Monument Type: Orange County Surveyor's 3 3/4"  
Aluminum Disk



NAVD88 (ft)	NGVD29 (ft)	Year Leveled
431.303	428.895	2006
431.303	428.895	1990

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 53 18.4	117 48 07.0

### Description:

DESCRIBED BY OCS 2003 - FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "2A-36-70", SET IN THE TOP OF A CONCRETE HEADWALL. MONUMENT IS LOCATED IN THE SOUTHWESTERLY CORNER OF THE INTERSECTION OF YORBA LINDA BOULEVARD AND OHIO STREET, 18 FT. WESTERLY OF THE WESTERLY CURB ALONG OHIO, 50 FT. SOUTHERLY OF THE SOUTH SOUTHWESTERLY CURB RETURN AND IN A LARGE GRASS FIELD IN FRONT OF UNITED METHODIST CHURCH. MONUMENT IS SET 2.0 FT. BELOW THE SURFACE OF OHIO STREET.

