

Designation: 2C-50-64

Date Destroyed:

Date Revised: 4/12/1999

GPS #: 1624

OCS Index Map: Q02-13

Page/Grid: 738/A-3

City / Location: Buena Park

Line #/SSN: 401/0340

Established By: LACO 1964

Monument Type: Bronze / Brass Disk



NAVD88 (ft)	NGVD29 (ft)	Year Levelled
151.448	149.017	2005
151.407	148.977	1999
151.444	149.014	1990

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 53 47.46	117 59 14.86

Description:

DESCRIBED BY OCS 2003 - FOUND 2.5 IN. LOS ANGELES COUNTY ENGINEER BRASS CAP STAMPED "BM-3-7A RE 5869-1961", SET IN THE NORTHEASTERLY CORNER OF A CONCRETE BRIDGE DECK. MONUMENT IS LOCATED IN THE NORTHWESTERLY CORNER OF THE INTERSECTION OF ROSECRANS AVENUE AND BEACH BOULEVARD, 90 FT. WESTERLY OF THE CENTER MEDIAN ALONG BEACH BOULEVARD 40 FT. NORTHERLY OF THE CENTER MEDIAN ALONG ROSECRANS AND AT THE EASTERLY END OF THE NORTHERLY GUARD RAIL ALONG BRIDGE. MONUMENT IS SET LEVEL WITH THE SIDEWALK.

