

Designation: 2C-80-69

Date Destroyed:

Date Revised:

GPS #:

OCS Index Map: Q07-02

Page/Grid: 769/H-2

City / Location: Anaheim

Line #/SSN: 403/0610

Established By: OCS 1969

Monument Type: Orange County Surveyor's 3 3/4"
Aluminum Disk



NAVD88 (ft)	NGVD29 (ft)	Year Leveled
240.944	238.536	2006
241.017	238.625	1988

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 51 15.44	117 50 26.32

Description:

DESCRIBED BY OCS 2003 - FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "2C-80-69", SET IN THE TOP OF A 6 IN BY 6 IN CONCRETE POST. MONUMENT IS LOCATED ALONG THE WESTERLY SIDE OF THE ATCHINSON TOPEKA AND SANTA FE RAILWAY, 550 FT. SOUTHWESTERLY OF THE CENTERLINE OF LA PALMA AVENUE, 18 FT. WESTERLY OF THE WESTERLY RAIL ALONG THE RAILWAY AND STEEL WITNESS POSTS 1.5 FT. NORTHERLY AND 1.5 FT. WESTERLY. MONUMENT IS SET 4 FT. BELOW THE LEVEL OF THE TRACKS.

