

Designation: 3A-106-77

Date Destroyed:

Date Revised:

GPS #:

OCS Index Map: Q12-05

Page/Grid: 859/G-3

City / Location: Irvine

Line #/SSN: 351/0010

Established By: OCS 1977

Monument Type: Orange County Surveyor's 3 3/4"
Aluminum Disk



NAVD88 (ft)	NGVD29 (ft)	Year Levelled
35.931	33.529	2003
36.221	33.809	1990

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 41 32.36	117 51 36.41

Description:

DESCRIBED BY OCS 2001 - FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "3A-106-77", SET IN THE SOUTHWEST CORNER OF A 4.5 FT. BY 4.5 FT. CONCRETE PAD. MONUMENT IS LOCATED ALONG THE SOUTHWESTERLY SIDE OF REDHILL AVENUE, 0.35 MILES NORTHEASTERLY OF THE INTERSECTION WITH MAIN STREET AND 41.8 FT. SOUTHWESTERLY OF THE SOUTHERLY CURB FACE ALONG REDHILL AVENUE. MONUMENT IS DOWN 3.0 FT. LOWER THAN ROAD SURFACE.

