

## Designation: 3A-115-79

Date Destroyed:

Date Revised: 7/2/2007

GPS #:

OCS Index Map: Q07-11

Page/Grid: 800/E-5

City / Location: Cowan Heights

Line #/SSN: 351/0180

Established By: OCS 1979

Monument Type: Orange County Surveyor's 3 3/4"  
Aluminum Disk



NAVD88 (ft)	NGVD29 (ft)	Year Leveled
339.645	337.219	2010
339.620	337.194	1991

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 46 59.82348	117 47 45.16466

### Description:

DESCRIBED BY OCS 2002 - FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "3A-115-79", SET IN THE TOP OF A 6 IN. BY 6 IN. CONCRETE POST. MONUMENT IS LOCATED ALONG THE WESTERLY SIDE OF CRAWFORD CANYON, 165 FT. NORTHERLY OF THE CENTERLINE OF BREA GLENN, 37 FT. WESTERLY OF THE CENTERLINE OF CRAWFORD CANYON. MONUMENT IS SET UP 0.3 FT. ABOVE THE GROUND.

