

Designation: 3B-59-68

Date Destroyed:

Date Revised:

GPS #:

OCS Index Map: Q17-15

Page/Grid: 952/C-7

City / Location: San Juan Capistrano

Line #/SSN: 402/0100

Established By: OCS 1968

Monument Type: Orange County Surveyor's 3 3/4"
Aluminum Disk



NAVD88 (ft)	NGVD29 (ft)	Year Leveled
137.354	135.039	1990

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 30 30.81	117 39 57.16

Description:

DESCRIBED BY OCS 2003 - FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "3B-59-68", SET IN THE NORTHWESTERLY CORNER OF A 4 FT. BY 7 FT. CONCRETE DROP INLET. MONUMENT IS LOCATED IN THE NORTHEASTERLY CORNER OF THE INTERSECTION OF LA ZANJA AND CAMINO CAPISTRANO, 264 FT. NORTHERLY OF THE CENTERLINE OF LA ZANJA AND 32.7 FT. EASTERLY OF THE CENTERLINE OF CAMINO CAPISTRANO. MONUMENT IS SET LEVEL WITH THE TOP OF THE CURB.

