

### Designation: 3B-95-82

Date Destroyed:

Date Revised: 4/9/2014

GPS #:

OCS Index Map: Q12-08

Page/Grid: 860/G-3

City / Location: Irvine

Line #/SSN: 402/0440

Established By: OCS 1982

Monument Type: Orange County Surveyor's 3 3/4"  
Aluminum Disk



NAVD88 (ft)	NGVD29 (ft)	Year Leveled
110.843	108.452	2014
110.895	108.501	2003
110.855	108.460	1991

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 41 23.7	117 46 48.5

### Description:

DESCRIBED BY OCS 2002 - FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "3B-95-82", SET IN THE TOP OF A 6 IN. BY 6 IN. CONCRETE POST. MONUMENT IS LOCATED ALONG THE SOUTHERLY SIDE OF THE ATCHINSON TOPEKA AND SANTA FE RAILWAY, 0.5 MILES NORTHWESTERLY OF THE CENTERLINE OF JEFFREY ROAD, 48 FT. SOUTHERLY OF THE SOUTH RAIL ALONG THE RAILWAY, 105 FT. NORTHWESTERLY OF THE CENTERLINE OF CLARK STREET PROJECTED TO THE NORTHEAST AND 1 FT. NORTHERLY OF A 5 FT. HIGH CHAIN LINK FENCE ALONG RAILROAD RIGHT OF WAY. MONUMENT IS SET LEVEL WITH THE GROUND.

