

Designation: 3E-90-71

Date Destroyed:

Date Revised:

GPS #:

OCS Index Map: Q17-04

Page/Grid: 922/D-1

City / Location: Mission Viejo

Line #/SSN: 355/0010

Established By: OCS 1971

Monument Type: Orange County Surveyor's 3 3/4"
Aluminum Disk



NAVD88 (ft)	NGVD29 (ft)	Year Leveled
470.908	468.559	1990

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 36 08.96	117 39 22.35

Description:

DESCRIBED BY OCS 2003 - FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "3E-90-71", SET IN THE SOUTHEASTERLY CORNER OF A 4 FT. BY 8 FT. CONCRETE CATCH BASIN. MONUMENT IS LOCATED IN THE NORTHWESTERLY CORNER OF THE INTERSECTION OF MARGUERITE PARKWAY AND ALDEANO DRIVE, 62 FT. NORTHEASTERLY OF THE CENTERLINE OF ALDEANO DRIVE AND 38.5 FT. NORTHWESTERLY OF THE CENTER MEDIAN ALONG MARGUERITE. MONUMENT IS SET LEVEL WITH THE SIDEWALK.

