

### Designation: 3H-22-03

Date Destroyed:

Date Revised: 9/11/2003

GPS #:

OCS Index Map: Q12-07

Page/Grid: 860/E-2

City / Location: Irvine

Line #/SSN: 358/0100

Established By: OCS 2003

Monument Type: Orange County Surveyor's 3 3/4"  
Aluminum Disk



NAVD88 (ft)	NGVD29 (ft)	Year Levelled
56.344	53.946	2003

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 41 56.05	117 47 35.80

### Description:

DESCRIBED BY OCS 2003 - FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "3H-22-03", SET IN THE NORTHERLY CORNER OF A 5 FT. BY 15 FT. CONCRETE CATCH BASIN. MONUMENT IS LOCATED ALONG THE SOUTHERLY SIDE OF CULVER DRIVE, 0.55 MILES NORTHEASTERLY OF THE CENTERLINE OF IRVINE CENTER DRIVE, 46 FT. SOUTHEASTERLY OF THE CENTERLINE OF CULVER DRIVE AND 80 FT. SOUTHWESTERLY OF THE CENTERLINE OF THE B.N.S.F. RAILWAY OVERCROSSING. MONUMENT IS SET LEVEL WITH THE SIDEWALK.

