

Designation: 3P-17-68

Date Destroyed: **6/17/1999**

Date Revised: 4/20/2014

GPS #:

OCS Index Map: Q16-12

Page/Grid: 950/H-4

City / Location: Laguna Beach

Line #/SSN: 400/0410

Established By: OCS 1968

Monument Type: Orange County Surveyor's 3 3/4"
Aluminum Disk

NO PHOTO

NAVD88 (ft)	NGVD29 (ft)	Year Leveled
63.658	61.321	1988

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 31 57.11	117 46 32.12

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: ORIGINALLY RECOVERY NOTE BY UNITED STATES POWER SQUADRON 1990 1.5 KILOMETERS (0.95 MILE) SOUTHEAST ALONG STATE HIGHWAY 1 FROM THE "T" JUNCTION OF BROADWAY (RTE 133) IN LAGUNA BEACH, SET AT THE EAST CORNER OF THE INTERSECTION OF CRESS STREET, SET AT THE NORTH CORNER OF A CATCH BASIN, 14.9 METERS (48.9 FT.) NORTHEAST OF THE CENTERLINE OF STATE HIGHWAY 1, 6.1 METERS (20 FT.) SOUTHEAST OF THE CENTERLINE OF CRESS STREET, 1.4 METERS (4.6 FT.) SOUTHWEST OF A POWER POLE, THE STATION IS LEVEL WITH THE HEIGHT OF THE STREET.

NO LOCATION MAP