

Designation: 3W-19-72

Date Destroyed: 9/26/1995

Date Revised: 4/20/2014

GPS #:

OCS Index Map: Q17-16

Page/Grid: 952/G-6

City / Location: San Juan Capistrano

Line #/SSN: 370/0390

Established By: OCS 1972

Monument Type: Orange County Surveyor's 3 3/4"
Aluminum Disk

NO PHOTO

NAVD88 (ft)	NGVD29 (ft)	Year Leveled
164.545	162.231	1990

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 31 00.76	117 37 47.42

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: ORIGINALLY DESCRIBED BY OCS 1972 FROM THE SAN DIEGO FREEWAY (I-5) PROCEED 2 MILES EAST ON ORTEGA HIGHWAY (STATE HIGHWAY 74) TO THE ENTRANCE ROAD TO SAN JUAN CREEK RANCH ON SOUTH SIDE OF ORTEGA HIGHWAY, SET AT THE NORTH SIDE OF ORTEGA HIGHWAY, 2 FT. EAST OF A PADDLEBOARD MARKED "ORANGE COUNTY CONTROL STATION", 32.3 FT. NORTH OF THE CENTER STRIPE OF ORTEGA HIGHWAY, 66 FT. NORTHERLY FROM THE POST FOR THE "SAN JUAN CREEK STABLES" SIGN ON SOUTH SIDE OF ORTEGA HIGHWAY, 23 FT. NORTHEAST OF THE CENTERLINE PROLONGATION TO THE NORTH OF THE ROAD INTO THE RANCH, 39 FT. EASTERLY OF A 3 FT. DIAMETER PEPPER TREE ON NORTH SIDE OF ORTEGA HIGHWAY, 16 FT. WESTERLY FROM A CLUMP OF 3 PEPPERTREES ON NORTH SIDE OF ORTEGA HIGHWAY, 18.5 FT. NORTHWEST OF A 24 INCH DIAMETER SEWER MANHOLE ON NORTH SHOULDER, 76.5 FT. NORTHEAST FROM POWER POLE #25678 1 FT. ABOVE GROUND.

NO LOCATION MAP