

Designation: CM-35-81

Date Destroyed:

Date Revised:

GPS #:

OCS Index Map: Q11-11

Page/Grid: 858/H-5

City / Location: Costa Mesa

Line #/SSN: 558/0030

Established By: OCS 1981

Monument Type: Orange County Surveyor's 3 3/4"
Aluminum Disk



NAVD88 (ft)	NGVD29 (ft)	Year Leveled
51.696	49.294	2005
51.778	49.365	1992

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 40 49.96	117 55 52.63

Description:

DESCRIBED BY OCS 2001 - FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "CM-35-81", SET IN THE NORTHWEST CORNER OF A 4 FT. BY 5 FT. CONCRETE EDISON VAULT. MONUMENT IS LOCATED IN THE NORTHWEST CORNER OF THE INTERSECTION OF MESA VERDE DRIVE WEST AND COUNTRY CLUB DRIVE, 27 FT. WESTERLY OF THE CENTERLINE OF COUNTRY CLUB DRIVE AND 28 FT. NORTHERLY OF A STREET STANDARD #1927928E. MONUMENT IS SET LEVEL WITH THE SIDEWALK.

