

## Designation: GRAHAM-11-74

Date Destroyed:

Date Revised:

GPS #: W104

OCS Index Map: Q10-07

Page/Grid: 857/E-1

City / Location: Huntington Beach

Line #/SSN: 624/0010

Established By: OCS 1974

Monument Type: Orange County Surveyor's 3 3/4"  
Aluminum Disk



| NAVD88 (ft) | NGVD29 (ft) | Year Leveled |
|-------------|-------------|--------------|
| 14.767      | 12.351      | 2014         |
| 14.767      | 12.351      | 2005         |
| 14.948      | 12.513      | 1992         |
|             |             |              |
|             |             |              |

| For Reconnaissance Only! |                     |
|--------------------------|---------------------|
| Latitude (30' +/-)       | Longitude (30' +/-) |
| 33 42 38.5               | 118 01 57.7         |

### Description:

DESCRIBED BY OCS 2003- FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "GRAHAM-11-74", SET IN THE TOP OF A CONCRETE POST. MONUMENT IS LOCATED IN THE NORTHWESTERLY CORNER OF THE INTERSECTION OF GRAHAM STREET AND THE GARDEN GROVE WINTERSBURG CHANNEL, 0.3 MILES SOUTHERLY OF WARNER AVENUE, 25 FT. NORTHERLY OF THE NORTHERLY END OF THE WESTERLY GUARD RAIL ALONG BRIDGE AND 35 FT. WESTERLY OF THE CENTERLINE OF GRAHAM. MONUMENT IS SET LEVEL WITH THE SIDEWALK.

