

Designation: HB-173-69

Date Destroyed:

Date Revised:

GPS #:

OCS Index Map: Q10-04

Page/Grid: 827/G-5

City / Location: Huntington Beach

Line #/SSN: 626/0050

Established By: OCS 1969

Monument Type: Orange County Surveyor's 3 3/4"
Aluminum Disk



NAVD88 (ft)	NGVD29 (ft)	Year Leveled
13.848	11.432	2005
13.976	11.539	1989

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 43 49.43	118 00 56.16

Description:

DESCRIBED BY OCS 2002 - FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "HB-173-69", SET IN THE NORTHEAST CORNER OF A 5 FT. BY 22 FT. CONCRETE CATCH BASIN. MONUMENT IS LOCATED IN THE NORTHWEST CORNER OF THE INTERSECTION OF EDWARDS STREET AND EDINGER AVENUE, 144 FT. NORTHERLY OF THE CENTERLINE OF EDINGER AVENUE AND 32.5 FT. WESTERLY OF THE CENTERLINE OF EDWARDS STREET. MONUMENT IS SET LEVEL WITH THE SIDEWALK.

