

Designation: HPGN-12-02

Date Destroyed:

Date Revised:

GPS #: 1202

OCS Index Map: Q20-03

Page/Grid: 972/A-6

City / Location: Dana Point

Line #/SSN: 402/0040

Established By: CDH 1990

Monument Type: Stainless Steel Rod



NAVD88 (ft)	NGVD29 (ft)	Year Leveled
23.700	21.403	1990

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 28 09.54532	117 40 49.59814

Description:

DESCRIBED BY OCS 2003 - FD 3-D TOP SECURITY ROD MONUMENT DRIVEN INTO THE GROUND WITH A 2 1/2" ALUMINUM DISK SET 0.25' BELOW ACCESS COVER, SAID ACCESS COVER STAMPED "CALIF. DEPT. OF TRANSPORTATION SURVEY MONUMENT HPGN". THE 2 1/2" CALIF. DEPT. OF TRANSPORTATION ALUMINUM DISK IS STAMPED "HPGN-CALIF. STA 12-02 1991", THE MONUMENT LID IS FLUSH WITH GROUND LEVEL. TO REACH THE STATION FROM THE INTERSECTION OF DEL OBISPO STREET AND STATE HIGHWAY 1 (PACIFIC COAST HIGHWAY) IN CAPISTRANO BEACH, GO SOUTHEASTERLY FOR 0.3 MI (0.5 KM) ON PACIFIC COAST HIGHWAY (STAYING TO THE RIGHT), TO THE ROAD ALONG THE EASTERLY LEVEE OF SAN JUAN CREEK. TURN LEFT AND GO NORTHERLY FOR 0.4 MI (0.6 KM) ALONG THE LEVEE TO A GRAVEL ROAD AND A BREAK IN THE FENCE ON THE RIGHT. TURN RIGHT AND GO EAST FOR 0.02 MI (0.03 KM) TO THE SOUTHWEST CORNER OF THE FENCED CHANNEL AND THE STATION. LOCATED 30.8 FT.(9.4 M) SOUTH OF THE NORTHWEST CORNER OF THE FENCE, 4.25 FT.(1.30 M) SOUTHEAST OF A WITNESS POST WITH SIGN HPGN MON 12-02 AND 2.95 FT.(0.90 M) NORTHWEST OF THE SOUTHWEST CORNER OF THE

