

Designation: SA-183-70

Date Destroyed:

Date Revised:

GPS #:

OCS Index Map: Q06-16

Page/Grid: 829/B-2

City / Location: Santa Ana

Line #/SSN: 717/0010

Established By: OCS 1970

Monument Type: Orange County Surveyor's 3 3/4"
Aluminum Disk



NAVD88 (ft)	NGVD29 (ft)	Year Leveled
87.371	84.956	2010
87.557	85.119	1992

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 45 05.49	117 54 09.33

Description:

DESCRIBED BY OCS 2001 - FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "SA-183-70", SET IN THE SOUTHWEST CORNER OF A 5FT. BY 14FT. CONCRETE CATCH BASIN. MONUMENT IS LOCATED IN THE NORTHEAST CORNER OF THE INTERSECTION OF FAIRVIEW STREET AND CIVIC CENTER DRIVE, 85.5 FT. EAST OF THE PROLONGATION OF THE EAST CURB OF FAIRVIEW STREET AND 40.5 FT. NORTHERLY OF THE CENTERLINE OF CIVIC CENTER DRIVE. MONUMENT IS LEVEL WITH THE SIDEWALK.

