

Designation: SA-286-75

Date Destroyed:

Date Revised:

GPS #:

OCS Index Map: Q11-04

Page/Grid: 829/C-3

City / Location: Santa Ana

Line #/SSN: 725/0040

Established By: OCS 1975

Monument Type: Orange County Surveyor's 3 3/4"
Aluminum Disk



NAVD88 (ft)	NGVD29 (ft)	Year Levelled
82.422	80.008	2010
82.592	80.149	1992

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 44 44.24	117 53 34.81

Description:

DESCRIBED BY OCS 2001 - FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "SA-286-75", SET IN THE SOUTHWEST CORNER OF A 4FT. BY 15FT. CONCRETE CATCH BASIN. MONUMENT IS LOCATED IN THE NORTHEAST CORNER OF THE INTERSECTION OF RAITT STREET AND FIRST STREET, 32.8FT. EASTERLY OF THE CENTERLINE OF RAITT STREET AND 3.8FT. NORTHERLY OF THE NORTH END OF THE NORTHEAST CURB RETURN ALONG FIRST STREET. MONUMENT IS SET LEVEL WITH SIDEWALK.

