

Designation: 1A-129-74

Date Destroyed:

Date Revised:

GPS #:

OCS Index Map: Q05-06

Page/Grid: 797/A-1

City / Location: Los Alamitos

Line #/SSN: 401/0130

Established By: OCS 1974

Monument Type: Orange County Surveyor's 3 3/4"
Aluminum Disk



NAVD88 (ft)	NGVD29 (ft)	Year Leveled
41.287	38.867	2005
41.394	38.907	1994

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 49 03.89	118 04 06.91

Description:

DESCRIBED BY OCS 2002 - FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "1A-129-74" SET IN THE TOP CORNER OF A CONCRETE OVERPASS. MONUMENT IS LOCATED IN THE NORTHEASTERLY CORNER OF THE INTERSECTION OF BALL ROAD AND THE COYOTE CREEK OVERPASS, 0.35 MILES WESTERLY OF THE CENTERLINE OF BLOOMFIELD AVENUE, 51 FT. NORTHERLY OF THE CENTERLINE OF BALL ROAD, 147 FT. EASTERLY OF THE CENTERLINE OF THE COYOTE CREEK CHANNEL AND 24 FT. NORTHEASTERLY OF AN OCS REFERENCE MARK. MONUMENT IS SET LEVEL WITH THE SIDEWALK. - NOTE: OCS REFERENCE MARK HAS STAMPING "RM-3 1974 1A-129-74" AND IS NOT TO BE CONFUSED WITH OCS BENCHMARK "1A-129-74".

