

Designation: 1A-130-74

Date Destroyed:

Date Revised:

GPS #:

OCS Index Map: Q05-07

Page/Grid: 767/B-5

City / Location: Cypress

Line #/SSN: 401/0180

Established By: OCS 1974

Monument Type: Orange County Surveyor's 3 3/4"
Aluminum Disk



NAVD88 (ft)	NGVD29 (ft)	Year Leveled
39.678	37.256	2005
39.768	37.302	1994

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 50 20.43	118 03 05.22

Description:

DESCRIBED BY OCS 2002 - FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "1A-130-74", SET IN THE SOUTHWESTERLY CORNER OF A 4 FT. BY 5 FT. CONCRETE CATCH BASIN. MONUMENT IS LOCATED ALONG THE NORTHERLY SIDE OF CRESCENT AVENUE, 0.3 MILES WESTERLY ALONG CRESCENT FROM THE CENTERLINE OF MOODY STREET AND 34 FT. NORTHERLY OF THE CENTERLINE OF CRESCENT. MONUMENT IS SET LEVEL WITH THE SIDEWALK.

