

Designation: 1B-104-04

Date Destroyed:

Date Revised: 4/29/2004

GPS #:

OCS Index Map: Q06-11

Page/Grid: 798/H-2

City / Location: Anaheim

Line #/SSN: 152/0290

Established By: OCS 2004

Monument Type: Orange County Surveyor's 3 3/4"
Aluminum Disk



NAVD88 (ft)	NGVD29 (ft)	Year Levelled
126.945	124.527	2005
127.062	124.607	2004

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 48 12.51	117 55 25.18

Description:

DESCRIBED BY OCS 2004 - FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "1B-104-04", SET IN THE SOUTHEASTERLY CORNER OF A 7.3 FT. BY 4.5 FT. CONCRETE CATCH BASIN. MONUMENT IS LOCATED IN THE NORTHEASTERLY CORNER OF THE INTERSECTION OF KATELLA AVENUE AND WEST STREET 58 FT. NORTHERLY OF THE CENTERLINE OF KATELLA AVENUE AND 102 FT. EASTERLY OF THE CENTERLINE OF WEST STREET. MONUMENT IS SET LEVEL WITH THE SIDEWALK

