

Designation: 1H-106-69

Date Destroyed:

Date Revised:

GPS #:

OCS Index Map: Q10-04

Page/Grid: 827/F-7

City / Location: Huntington Beach

Line #/SSN: 158/0110

Established By: OCS 1969

Monument Type: Orange County Surveyor's 3 3/4"
Aluminum Disk



NAVD88 (ft)	NGVD29 (ft)	Year Leveled
6.714	4.298	2014
6.714	4.298	2005
6.925	4.488	1989

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 43 13.30	118 01 27.06

Description:

DESCRIBED BY OCS 2002 - FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "1H-106-69", SET IN THE SOUTHEAST CORNER OF A 7 FT. BY 25 FT. CONCRETE CATCH BASIN. MONUMENT IS LOCATED IN THE NORTHWEST CORNER OF THE INTERSECTION OF DONLYN DRIVE AND SPRINGDALE STREET, 42 FT. WESTERLY OF THE CENTERLINE OF SPRINGDALE STREET AND 97 FT. NORTHERLY OF THE CENTERLINE OF DONLYN DRIVE. MONUMENT IS SET LEVEL WITH THE SIDEWALK.

