

Designation: 1H-113-70

Date Destroyed:

Date Revised:

GPS #:

OCS Index Map: Q05-16

Page/Grid: 797/G-6

City / Location: Garden Grove

Line #/SSN: 158/0210

Established By: OCS 1970

Monument Type: Orange County Surveyor's 3 3/4"
Aluminum Disk



NAVD88 (ft)	NGVD29 (ft)	Year Leveled
45.447	43.029	2005
45.613	43.151	1989

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 46 39.66	118 00 39.25

Description:

DESCRIBED BY OCS 2002 - FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "1H-113-70", SET IN THE SOUTHEASTERLY CORNER OF A 3.5 FT. BY 8.5 FT. CONCRETE CATCH BASIN. MONUMENT IS LOCATED IN THE SOUTHWESTERLY CORNER OF THE INTERSECTION OF KNOTT AVENUE AND STANFORD AVENUE, 33.5 FT. WESTERLY OF THE CENTERLINE OF KNOTT AND 72.5 FT. SOUTHERLY OF THE CENTERLINE OF STANFORD. MONUMENT IS SET LEVEL WITH THE SIDEWALK.

