

Designation: 1K-26-70

Date Destroyed: **4/10/2012**

Date Revised:

GPS #:

OCS Index Map: Q07-05

Page/Grid: 769/F-5

City / Location: Orange

Line #/SSN: 160/0070

Established By: OCS 1970

Monument Type: Orange County Surveyor's 3 3/4"
Aluminum Disk



NAVD88 (ft)	NGVD29 (ft)	Year Leveled
215.294	212.880	2006
215.322	212.914	1990

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 50 06.0	117 51 44.0

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: DESCRIBED BY OCS 2002 - FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "1K-26-70", SET IN THE NORTHWESTERLY CORNER OF A 1 FT. BY 1 FT. CONCRETE FOOTING FOR A 10 FT. TALL STEEL VENT PIPE. MONUMENT IS LOCATED IN THE SOUTHWESTERLY CORNER OF THE INTERSECTION OF BATAVIA STREET AND LINCOLN AVENUE 20 FT. SOUTHWESTERLY OF THE SOUTHWEST CURB ALONG LINCOLN AND 111 FT. NORTHWESTERLY OF THE PROLONGATION OF THE WESTERLY CURB ALONG BATAVIA. MONUMENT IS SET 4 FT. BELOW LINCOLN AVENUE.

NO
LOCATION
MAP