

Designation: 1L-40-81

Date Destroyed:

Date Revised:

GPS #:

OCS Index Map: Q11-10

Page/Grid: 858/F-7

City / Location: Huntington Beach

Line #/SSN: 640/0040

Established By: OCS 1981

Monument Type: Orange County Surveyor's 3 3/4"
Aluminum Disk



NAVD88 (ft)	NGVD29 (ft)	Year Leveled
31.371	28.965	2005
31.655	29.243	1992

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 40 21.3	117 56 46.2

Description:

DESCRIBED BY OCS 2002 - FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "1L-40-81", SET IN THE TOP OF A 4 IN. BY 4 IN. CONCRETE POST. MONUMENT IS LOCATED IN THE NORTHWEST CORNER OF THE INTERSECTION OF ADAMS AVENUE AND THE SANTA ANA RIVER CROSSING, 9 FT. NORTHERLY OF THE NORTH CURB ALONG ADAMS AND 38.0 FT. WESTERLY OF THE WEST END OF THE NORTHERLY GUARDRAIL ON BRIDGE. MONUMENT IS SET 3.0 FT. BELOW THE SIDEWALK.

