

Designation: 1L-62-82

Date Destroyed:

Date Revised:

GPS #:

OCS Index Map: Q07-02

Page/Grid: 769/H-3

City / Location: Orange

Line #/SSN: 403/0590

Established By: OCS 1982

Monument Type: Orange County Surveyor's 3 3/4"
Aluminum Disk



NAVD88 (ft)	NGVD29 (ft)	Year Leveled
243.534	241.123	2006
243.605	241.220	1988

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 50 45.91	117 50 36.01

Description:

DESCRIBED BY OCS 2002 - FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "1L-62-82", SET IN THE SOUTHERLY END OF A CONCRETE BRIDGE ABUTMENT. MONUMENT IS LOCATED IN THE SOUTHWESTERLY CORNER OF THE ATCHINSON TOPEKA AND SANTA FE RAILWAY CROSSING OF THE SANTA ANA RIVER, 9.7 FT. WESTERLY OF THE CENTERLINE OF THE RAILWAY AND BETWEEN THE CROSSING OF GLASSELL STREET AND TUSTIN AVENUE ALONG THE SOUTHERLY LEVEE OF THE RIVER. MONUMENT IS SET LEVEL WITH THE TOP OF THE BRIDGE DECK.

