

Designation: 2A-41-73

Date Destroyed:

Date Revised:

GPS #:

OCS Index Map: Q03-15

Page/Grid: 740/D-4

City / Location: Yorba Linda

Line #/SSN: 266/0010

Established By: OCS 1973

Monument Type: Orange County Surveyor's 3 3/4"
Aluminum Disk



NAVD88 (ft)	NGVD29 (ft)	Year Leveled
420.969	418.559	2006
421.002	418.592	1990

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 53 18.83	117 47 51.69

Description:

DESCRIBED BY OCS 2003 - FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "2A-41-73", SET IN THE NORTHEASTERLY CORNER OF A 4 FT. BY 4.5 FT. CONCRETE CATCH BASIN. MONUMENT IS LOCATED IN THE SOUTHEASTERLY CORNER OF THE INTERSECTION OF YORBA LINDA BOULEVARD AND PALM STREET, 38 FT. SOUTHERLY OF THE CENTERLINE OF YORBA LINDA AND 165 FT. EASTERLY OF THE CENTERLINE OF PALM. MONUMENT IS SET LEVEL WITH THE SIDEWALK.

