

Designation: 2C-70-68

Date Destroyed: **5/5/2010**

Date Revised:

GPS #:

OCS Index Map: Q02-10

Page/Grid: 738/C-1

City / Location: La Habra

Line #/SSN: 401/0390

Established By: OCS 1968

Monument Type: Orange County Surveyor's 3 3/4"
Aluminum Disk



NAVD88 (ft)	NGVD29 (ft)	Year Leveled
220.566	218.146	2005
220.566	218.146	1990

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 55 02.02	117 58 09.17

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: DESCRIBED BY OCS 2002 - FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "2C-70-68", SET IN THE NORTHEASTERLY END OF A 3 FT. BY 4 FT. CONCRETE CATCH BASIN LEADING INTO A FLOOD CHANNEL. MONUMENT IS LOCATED IN THE SOUTHWESTERLY CORNER OF THE INTERSECTION OF IMPERIAL HIGHWAY AND BEACH BOULEVARD, 42 FT. SOUTHERLY OF THE CENTERLINE OF IMPERIAL HIGHWAY AND 175 FT. WESTERLY ALONG IMPERIAL HIGHWAY FROM THE CENTERLINE OF BEACH BOULEVARD TO THE UNDERCROSSING OF A FLOOD CONTROL CHANNEL. MONUMENT IS SET LEVEL WITH THE SIDEWALK.

NO
LOCATION
MAP