

Designation: 2C-98-74

Date Destroyed: **3/13/2010**

Date Revised:

GPS #:

OCS Index Map: Q07-02

Page/Grid: 769/J-1

City / Location: Anaheim

Line #/SSN: 403/0620

Established By: OCS 1974

Monument Type: Orange County Surveyor's 3 3/4"
Aluminum Disk



NAVD88 (ft)	NGVD29 (ft)	Year Leveled
245.238	242.831	2006
245.301	242.914	1988

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 51 33.52	117 50 20.51

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: DESCRIBED BY OCS 2003 - FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "2C-98-74", SET IN THE TOP OF A 6 IN BY 6 IN CONCRETE POST. MONUMENT IS LOCATED IN THE SOUTHWESTERLY PORTION OF THE INTERSECTION OF TUSTIN AVENUE AND THE ATCHINSON TOPEKA AND SANTA FE RAILWAY, 54 FT. WESTERLY OF THE CENTERLINE OF THE RAILWAY, 60 FT. SOUTHWESTERLY OF THE CENTERLINE OF TUSTIN, 7.5 FT. WESTERLY OF A RAILWAY SEMAPHORE WITH DOUBLE RED LIGHTS AND 1.3 FT. SOUTHERLY OF A STEEL WITNESS POST. MONUMENT IS SET UP 0.2 FT. ABOVE THE GROUND.

NO
LOCATION
MAP