

Designation: 3JJ-16-90

Date Destroyed:

Date Revised:

GPS #:

OCS Index Map: Q13-15

Page/Grid: 892/A-2

City / Location: Lake Forest

Line #/SSN: 346/0080

Established By: OCS 1990

Monument Type: Orange County Surveyor's 3 3/4"
Aluminum Disk



NAVD88 (ft)	NGVD29 (ft)	Year Leveled
643.881	641.517	2004
643.881	641.517	1990

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 38 53.12	117 40 42.00

Description:

DESCRIBED BY OCS 2003 - FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "3JJ-16-90", SET IN THE SOUTHWESTERLY CORNER OF A 4.5 FT. BY 22 FT. CONCRETE CATCH BASIN. MONUMENT IS LOCATED ALONG THE SOUTHERLY SIDE OF LAKE FOREST DRIVE, 100 FT. SOUTHERLY OF THE CENTERLINE OF STERLING DRIVE AND 47 FT. EASTERLY OF THE CENTERLINE OF LAKE FOREST DRIVE. MONUMENT IS SET LEVEL WITH THE SIDEWALK.

