

## Designation: 3K-28A-68

Date Destroyed:

Date Revised: 6/27/2011

GPS #:

OCS Index Map: Q11-20

Page/Grid: 919/D-2

City / Location: Newport Beach

Line #/SSN: 406/0040

Established By: OCS 1968

Monument Type: Orange County Surveyor's 3 3/4"  
Aluminum Disk



NAVD88 (ft)	NGVD29 (ft)	Year Leveled
40.282	37.939	2011
40.336	37.999	1994

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 36 00.13448	117 52 39.85413

### Description:

DESCRIBED BY OCS 2003 - FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "3K-28A-68", SET IN THE SOUTHEASTERLY CORNER OF A 4 FT. BY 3.5 FT. CONCRETE CATCH BASIN. MONUMENT IS LOCATED IN THE NORTHEASTERLY CORNER OF THE INTERSECTION OF BAYSIDE DRIVE AND CARNATION AVENUE, 19 FT. NORTHERLY OF THE CENTERLINE OF CARNATION AND 48 FT. EASTERLY OF THE CENTERLINE OF BAYSIDE. MONUMENT IS SET LEVEL WITH THE SIDEWALK.

