

Designation: 3K-32-68

Date Destroyed:

Date Revised:

GPS #:

OCS Index Map: Q16-11

Page/Grid: 950/F-2

City / Location: Laguna Beach

Line #/SSN: 400/0450

Established By: OCS 1968

Monument Type: Orange County Surveyor's 3 3/4"
Aluminum Disk



NAVD88 (ft)	NGVD29 (ft)	Year Leveled
71.092	68.750	2004
71.092	68.750	1988

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 32 39.88	117 47 25.12

Description:

DESCRIBED BY OCS 2003 - FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "3K-32-68", SET IN THE TOP OF A CONCRETE POST. MONUMENT IS LOCATED IN THE SOUTHWESTERLY CORNER OF PACIFIC COAST HIGHWAY AND JASMINE STREET, 45 FT. WESTERLY OF THE CENTERLINE OF PCH, 13.1 FT. SOUTHERLY OF THE CENTERLINE OF JASMINE AND 17.7 FT. WESTERLY OF A STREET STANDARD. MONUMENT IS SET LEVEL WITH THE SIDEWALK.

