

Designation: 3KK-12A-80

Date Destroyed:

Date Revised:

GPS #:

OCS Index Map: Q08-05

Page/Grid: 771/C-4

City / Location: Unin., Orange Co.

Line #/SSN: 388/0050

Established By: OCS 1980

Monument Type: Orange County Surveyor's 3 3/4"
Aluminum Disk

NO PHOTO

NAVD88 (ft)	NGVD29 (ft)	Year Leveled
938.669	936.250	1991

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 50 24.8	117 43 57.4

Description:

DESCRIBED BY OCS 1991 FROM INTERSECTION OF CHAPMAN AVENUE AND JAMBOREE ROAD PROCEED NORTHERLY ON JAMBOREE ROAD 0.3 MILE TO OLD CHAPMAN AVENUE, PROCEED WESTERLY ON OLD CHAPMAN AVENUE 16.5 FT. TO GATE ON NORTHERLY SIDE OF ROAD, THENCE THRU GATE AND PROCEED ON DIRT ROAD 0.5 MILE CROSS CREEK AND IMMEDIATELY TAKE LEFT. FORK 0.7 MILE NORTHWEST PARALLELING CREEK DOWNSTREAM TO A LOCKED GATE, PROCEED THROUGH GATE 2.75 MILE NORTHEASTERLY IN WEIR CANYON TO A SMALL STREAM CROSSING HAVING CONCRETE TELEPHONE CONDUIT HEADWALL UPSTREAM, AND ROCK MASONRY HEADWALL AND APRON DOWNSTREAM, SHORT STEEP HILL JUST BEYOND CROSSING, 29.5 FT. EAST OF NORTH END OF UPSTREAM HEADWALL, 29.8 FT. NORTHEAST OF THE UPSTREAM END OF THE 30 INCH PIPE CULVERT, 36 FT. NORTHEAST OF CENTERLINE OF ROAD WITH PADDLEBOARD 1 FT. EAST OF MONUMENT.

