

Designation: 3RR-2-82

Date Destroyed:

Date Revised: 5/10/1999

GPS #:

OCS Index Map: Q20-06

Page/Grid: 971/H-7

City / Location: Dana Point

Line #/SSN: 376/0040

Established By: OCS 1982

Monument Type: Orange County Surveyor's 3 3/4"
Aluminum Disk



NAVD88 (ft)	NGVD29 (ft)	Year Leveled
16.260	13.961	1997

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 27 46.74	117 42 05.40

Description:

DESCRIBED BY OCS 2003 - FOUND 3 3/4" ALUMINUM BENCHMARK DISK STAMPED "3RR-2-82" SET IN THE SOUTHEAST CORNER OF A 4.0 FT. X 4.5 FT. CONCRETE CATCH BASIN. MONUMENT IS LOCATED APPROXIMATELY 0.5 MILES WESTERLY ALONG DANA POINT HARBOR DRIVE FROM IT'S INTERSECTION WITH DEL PRADO STREET, WERE TWO CONCRETE CATCH BASINS FALL RADIAL ACROSS SAID DRIVE, 35.8 FT. SOUTHERLY OF THE CENTERLINE OF DANA POINT HARBOR DRIVE, 112.2 FT. SOUTHWESTERLY OF STREET LIGHT POLE #225684GM20, 40.8 FT. SOUTHEASTERLY OF STREET LIGHT POLE #225685GM20, 40.6 FT. WESTERLY OF A "NO STOPPING AT ANY TIME" SIGN. MONUMENT IS SET LEVEL WITH THE SIDEWALK.

