

Designation: 3V-2-80

Date Destroyed:

Date Revised:

GPS #:

OCS Index Map: Q13-04

Page/Grid: 832/C-3

City / Location: Silverado Canyon

Line #/SSN: 369/0020

Established By: OCS 1980

Monument Type: Orange County Surveyor's 3 3/4"
Aluminum Disk



NAVD88 (ft)	NGVD29 (ft)	Year Leveled
1081.015	1078.625	1992

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 44 39.20	117 39 24.20

Description:

DESCRIBED BY OCS 2003 - FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "3V-2-80", SET IN THE TOP OF A CONCRETE POST. MONUMENT IS LOCATED ALONG THE SOUTHERLY SIDE OF SILVERADO CANYON ROAD, 1.05 MILES EASTERLY ALONG SILVERADO CANYON ROAD FROM THE CENTERLINE OF BLACK STAR CANYON ROAD, 38 FT. WESTERLY OF THE CENTERLINE OF SILVERADO CANYON ROAD, 1.0 FT. NORTHERLY OF A 2.5 FT. HIGH STUCCO WALL AND 14 FT. SOUTHERLY OF A POWER POLE #1041206H. MONUMENT IS SET LEVEL WITH THE GROUND.

