

Designation: 3W-30-72

Date Destroyed:

Date Revised: 5/28/2013

GPS #: 1445

OCS Index Map: Q18-10

Page/Grid: 953/C-3

City / Location: Unin., Orange Co.

Line #/SSN: 370/0270

Established By: OCS 1972

Monument Type: Orange County Surveyor's 3 3/4"
Aluminum Disk



NAVD88 (ft)	NGVD29 (ft)	Year Leveled
357.380	355.046	1990

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 32 04.71958	117 35 16.95884

Description:

DESCRIBED BY OCS 2013 - FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "3W-30-72", SET IN THE TOP OF A 6 IN. BY 6 IN. CONCRETE POST. MONUMENT IS LOCATED IN CANADA GOBENADORA. TO REACH MONUMENT FROM THE GATE INTO SAID CANYON (LATITUDE 33-31-27, LONGITUDE 117-35-45), PROCEED THRU GATE AND CONTINUE ALONG DIRT ROAD INTO CANADA GOBENADORA FOR 1.0 MILE. MONUMENT IS SET ON SMALL KNOLL, 220 FT. EASTERLY OF THE DIRT ROAD AND 2 FT. WESTERLY OF A STEEL WITNESS POST. MONUMENT IS SET 0.2 FT. ABOVE THE GROUND AND +/- 10 FT. ABOVE THE ROAD LEVEL.

